

Aesthetic appeal project 2010



Superior Shores Resort expansion

Project description

Superior Shores Resort on Highway 61 just north of Two Harbors added an exterior pool, hot tub, fire ring and patio area in the summer of 2010. The pool contractor did the concrete work which included shotcrete for a pool and hot tub along with decorative flatwork for the pool deck and fire ring area. The site constraints of working adjacent to an existing, fully operational resort during peak season called for extreme care in delivery and placement of concrete to minimize the disturbance at the resort.

Project dates

06/10 - 09/10

Special project challenges

The contractor, due to site access constraints, needed to pump the entire project with his trailer pump and a 2" diameter line. We had to find just the right concrete mix combination that could be pumped through that line. A 3/8" exterior mix was used along with a retarding admixture to allow the contractor the proper amount of time to place and finish the concrete. They also pumped the shotcrete and decorative flatwork with this mix and pump.

Team

Contractor: J and J Pools Owner: Superior Shores Resort

Ready mix supplier: Arrowhead Concrete

For more information about this project, contact Jeremy Carlson at jeremy@arrowheadconcreteworks.com.